

KINFRA INTERNATINAL APPAREL PARK THUMBA,TRIVANDRUM MOB:9744716000, 9388125675 Email:indograceproject@gmail.com www.indograce.in

TO, 20/04/2018

Dr. REENA RAVINDRAN TRIVANDRUM

Dear,

We are pleased to submit our lowest rate of quality work for your kind consideration and approval.

QUOTATION FOR ROOF FABRICATION –

DESCRIPTION OF WORKS: Four side slope average Area: 2200

(AAPOLO/GAINT ISI) 2.5 Inch round pipe for pillar(16kg), 3/1.5 inch square tube for(16kg) outside beam, inside tress work beam for 3/1.5"(16kg)Gp square tube, purling for 1 inch square tube of(5.5kg), primer with ALUMINIUM paint. pvc Chanel. patta self-drilling screw 20mm/55mm.

GI Trafford sheet .35 BUSHAN POWER OR JSW

Rate of work per square feet: 105/-

1. Four side 2200 SQFT *105Rs = 231000/-

2. Thovanam= 52 FT *120Rs =62240/-

3. TOTAL = 293240

TERMS AND CONDITION

PAYMENT:-50% as advance when material will reach your location and 25% middle of the works and balance amount client should be paid for after completion of works.

Taxes& duties: additional as per Govt. rule

DURATION:-15 working days after the agreement.

Scope of work: Does not include any civil work.

Measurement : (Sloping area) measuring after the completion of roof works.

ELECTRICITY: client should be providing electricity & approval from KSEB

We are agree to satisfied above mentioned terms and condition